

GPS #: 1515

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation: 3A-96-71

OCS Index Map: 2L

Page/Grid: 770/C-7

City / Location: Villa Park

Scale Factor: 0.99998921

Ellipsoid Red. Factor: 0.99998826

Combination Factor: 0.99997747

Convergence Angle: -00 51 23.74182

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 48 52.00332	117 48 31.72556	2243518.196	6088189.881	245.413
2007.00	33 48 52.01947	117 48 31.74245	2243519.85	6088188.48	

References: OCS FILE # OC96/7-5, GEODETIC UNIT

Description:

DESCRIBED BY OCS 2002 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "3A-96-71", SET IN THE TOP OF A 6 IN. BY 6 IN. CONCRETE POST. MONUMENT IS LOCATED IN THE NORTHEASTERLY CORNER OF THE INTERSECTION OF LEMON STREET AND SANTIAGO BOULEVARD, 31.5 FT. EASTERLY OF THE CENTERLINE OF LEMON AND 48.5 FT. NORTHERLY OF THE CENTERLINE OF SANTIAGO. MONUMENT IS SET UP 0.2 FT. ABOVE THE TOP OF THE CURB.

