

**GPS #:** 1516

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation: 3KK-5-71

OCS Index Map: 5LB

Page/Grid: 771/A-7

City / Location: Unin., Orange County

Scale Factor: 0.99998932

Ellipsoid Red. Factor: 0.99997443

Combination Factor: 0.99996374

Convergence Angle: -00 49 28.73475

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 48 54.51411	117 45 02.43821	2243512.897	6105850.442	534.376
2007.00	33 48 54.53046	117 45 02.45488	2243514.57	6105849.06	

References: OCS FILE # OC96/7-5, GEODETIC UNIT

**Description:**

FD 3 3/4" OCS ALUMINUM DISK STAMPED "3KK-5-71". LOCATED FROM THE INTER OF CHAPMAN AVE. AND JAMBOREE RD. PROCEED N'LY ON JAMBOREE RD. 0.3 MILE TO OLD CHAPMAN AVE., PROCEED W'LY ON OLD CHAPMAN AVE. 165' TO GATE ON N'LY SIDE OF OLD CHAPMAN RD., PROCEED THROUGH GATE ON DIRT RD. 0.5 OF A MILE CROSS CREEK AND IMMEDIATELY TAKE LEFT. FORK, 0.7 MILE WEST PARALLELING CREEK DOWNSTREAM TO LOCKED GATE, PROCEED THROUGH GATE N'LY IN WEIR CANYON 0.75 MILE TO A CREEK CROSSING, SET AT THE TOP OF A CONC. POST, 50' NE ALONG THE RD. FROM THE CREEK CROSSING, 60' NW OF THE CENTER OF THE RD., 0.5' ABOVE THE GROUND, STEEL WITNESS POST, 1' WEST.

