

GPS #: 1517

Date Destroyed: 8/1/2012

Date Revised: 4/23/1996

Benchmark Designation: 2A-29-69

OCS Index Map: 1L

Page/Grid: 740/C-7

City / Location: Anaheim

Scale Factor: 0.99999716

Ellipsoid Red. Factor: 0.99999286

Combination Factor: 0.99999002

Convergence Angle: -00 51 33.78781

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 51 57.75868	117 48 50.00703	2262316.257	6086929.167	149.124
2007.00	33 51 57.77522	117 48 50.02354	2262317.95	6086927.80	

References: OCS FILE # OC96/7-5, GEODETIC UNIT

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: DESCRIBED BY OCS 2003 FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "2A-29-69", SET IN THE SOUTHERLY END OF A CONCRETE HEADWALL. MONUMENT IS LOCATED IN THE SOUTHWESTERLY CORNER OF THE INTERSECTION OF ORANGETHORPE AVENUE AND THE CENTERLINE OF HOLBROOK STREET PROLONGED TO THE SOUTH, 33 FT. SOUTHERLY OF THE EASTBOUND LANES OF ORANGETHORPE, 135.8 FT. WESTERLY OF THE EXTENDED CENTERLINE OF HOLBROOK AND 19.4 FT. NORTHERLY OF THE NORTHERLY RAIL ALONG THE ATCHINSON/TOPEKA/SANTA FE RAILWAY. MONUMENT IS SET 3 FT. BELOW THE LEVEL OF THE TRACKS.

NO
LOCATION
MAP