

GPS #: 1520

Date Destroyed: 10/9/2001
Date Revised: 4/23/1996
Benchmark Designation: 2A-33-70
OCS Index Map: 1L
Page/Grid: 740/B-3
City / Location: Yorba Linda

Scale Factor: 1.00000175
Ellipsoid Red. Factor: 0.99998733
Combination Factor: 0.99998908
Convergence Angle: -00 51 45.53340

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 53 37.32597	117 49 11.38139	2272407.087	6085278.490	264.727
2007.00	33 53 37.34241	117 49 11.39818	2272408.77	6085277.10	

References: OCS FILE # OC96/7-5, GEODETIC UNIT

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 3 3/4" OCS ALUMINUM DISK STAMPED "2A-33-70". LOCATED IN THE NE PART OF THE INTER OF IMPERIAL HWY. AND EUREKA AVE., 58' SE ALONG THE NE CURB OF IMPERIAL HWY. FROM THE EAST NE CURB RETURN, 4' SE ALONG THE NE CURB OF IMPERIAL HWY. FROM THE SE EDGE OF THE DR.WAY INTO 18052 IMPERIAL HWY., SET IN THE TOP OF A CONC. POST AT BACK OF CURB AND 0.1' LOWER.

NO
LOCATION
MAP