

GPS #: **1526**

Date Destroyed:
Date Revised: 4/23/1996
Benchmark Designation: U-348
OCS Index Map: 1L
Page/Grid: 709/E-3
City / Location: Unin., Los Angeles County

Scale Factor: 1.00001153
Ellipsoid Red. Factor: 0.99997970
Combination Factor: 0.99999124
Convergence Angle: -00 53 21.59169

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 56 54.46955	117 52 06.18615	2292558.756	6070853.652	424.140
2007.00	33 56 54.48649	117 52 06.20323	2292560.49	6070852.24	

References: OCS FILE # OC96/7-5, GEODETIC UNIT

Description:

FD 3 3/4" OCS ALUMINUM DISK STAMPED "U-348"
 LOCATED 0.8 OF A MILE NE ALONG BREA BLVD.
 FROM ITS INTER WITH TONNER CANYON RD., 43' SE
 OF THE CENTERLINE OF BREA BLVD., 24' EAST OF
 POWER POLE #788930H, 28' SW OF A CONC.
 HEADWALL, 165' NE OF BENCHMARK #V-348, 1.5' NE
 OF A METAL WITNESS POST, ON THE TOP OF A 1' X
 1' CONC. POST, 6' BELOW THE RD. LEVEL.

