

GPS #: 1527

Date Destroyed:
Date Revised: 4/23/1996
Benchmark Designation: 2A-44-83
OCS Index Map: 1L
Page/Grid: 740/G-4
City / Location: Yorba Linda

Scale Factor: 1.00000130
Ellipsoid Red. Factor: 0.99997920
Combination Factor: 0.99998050
Convergence Angle: -00 50 21.13081

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 53 27.76879	117 46 37.78742	2271248.800	6098210.741	434.628
2007.00	33 53 27.78531	117 46 37.80385	2271250.49	6098209.38	

References: OCS FILE # OC96/7-5, GEODETIC UNIT

Description:

DESCRIBED BY OCS 2003 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "2A-44-83", SET IN THE SOUTHWESTERLY CORNER OF A 5.4 FT. BY 6.4 FT. CONCRETE EDISON VAULT. MONUMENT IS LOCATED IN THE NORTHWESTERLY CORNER OF THE INTERSECTION OF YORBA LINDA BOULEVARD AND VILLAGE CENTER DRIVE 87 FT. WESTERLY OF THE CENTERLINE OF VILLAGE CENTER DRIVE AND 44 FT. NORTHERLY OF THE CENTERLINE OF YORBA LINDA BOULEVARD. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

