

GPS #: **1528**

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation: 3K-47-92

OCS Index Map: 5LA

Page/Grid: 919/G-3

City / Location: Costa Mesa

Scale Factor: 0.99996405

Ellipsoid Red. Factor: 0.99999855

Combination Factor: 0.99996261

Convergence Angle: -00 53 01.72388

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 35 22.11652	117 51 30.03114	2161892.331	6071884.182	30.220
2007.00	33 35 22.13291	117 51 30.04826	2161894.01	6071882.76	

References: OCS FILE # OC96/7-5, GEODETIC UNIT

Description:

DESCRIBED BY OCS 2002 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "3K-47-92", SET IN THE EASTERLY CORNER OF A 4 FT. BY 4 FT. CONCRETE CATCH BASIN. MONUMENT IS LOCATED IN THE NORTHEASTERLY CORNER OF THE INTERSECTION OF PACIFIC COAST HIGHWAY AND CAMEO HIGHLANDS, 40 FT. NORTHERLY OF THE CENTERLINE OF PCH AND 80 FT. EASTERLY OF THE CENTERLINE OF CAMEO HIGHLANDS. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

