

**GPS #:** 1530

Date Destroyed:  
Date Revised: 4/23/1996  
Benchmark Designation: D-1416  
OCS Index Map: 5LA  
Page/Grid: 859/E-5  
City / Location: Costa Mesa

Scale Factor: 0.99997264  
Ellipsoid Red. Factor: 1.00000362  
Combination Factor: 0.99997625  
Convergence Angle: -00 53 26.96610

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 40 58.61929	117 52 15.96638	2195961.793	6068527.615	-75.623
2007.00	33 40 58.63566	117 52 15.98320	2195963.47	6068526.22	

References: OCS FILE # OC96/7-5, GEODETIC UNIT

**Description:**

FD 3 3/4" OCS ALUMINUM DISK STAMPED "D-1416". LOCATED 270' WEST ALONG 6TH ST. FROM THE POST OFFICE IN SANTA ANA, THENCE 4.4 MILES SOUTH ALONG MAIN ST., THENCE 0.6 MILE WEST ALONG REDHILL AVE., TO THE APPROXIMATE MIDWAY POINT BETWEEN McCORMICK ST. AND PULLMAN ST., SET IN THE S'LY CORNER OF A CATCH BASIN, 19.4' NW'LY OF WESTBOUND LN.S CENTERLINE, 15.4' SW'LY OF A POWER POLE, 3.3' EAST OF THE EAST EDGE OF A PACIFIC BELL MANHOLE, SET IN A LAWN LEVEL WITH THE ST.

