

**GPS #:** 1532

**Date Destroyed:** 7/7/1997  
**Date Revised:** 4/23/1996  
**Benchmark Designation:** L-782  
**OCS Index Map:** 5LA  
**Page/Grid:** 919/B-2  
**City / Location:** Newport Beach

**Scale Factor:** 0.99996522  
**Ellipsoid Red. Factor:** 1.00000507  
**Combination Factor:** 0.99997028  
**Convergence Angle:** -00 54 36.72063

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 36 14.60782	117 54 22.90415	2167426.322	6057346.238	-105.876
2007.00	33 36 14.62419	117 54 22.92135	2167428.00	6057344.81	

**References:** OCS FILE # OC96/7-5, GEODETIC UNIT

**Description:**

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 3 3/4" OCS ALUMINUM DISK STAMPED "L-782". LOCATED AT BALBOA, 0.7 OF A MILE EAST OF NEWPORT BEACH GRAMMAR SCHOOL, AT THE "T" JUNCTION OF BALBOA BLVD. AND ISLAND AVE., 44.8' SOUTH OF THE CENTER OF THE ENTRANCE DOOR TO THE NEWPORT HARBOR PUBLIC LIBRARY, 8.2' EAST OF THE EAST CURB OF ISLAND AVE., 5.4' NORTH OF THE NORTH CURB OF BALBOA BLVD., FLUSH WITH THE CONC. SIDEWALK, SET IN THE TOP OF A CONC. POST.