

GPS #: 1536

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation: 1F-160-92

OCS Index Map: 4LA

Page/Grid: 798/J-7

City / Location: Garden Grove

Scale Factor: 0.99998266

Ellipsoid Red. Factor: 1.00000107

Combination Factor: 0.99998373

Convergence Angle: -00 55 04.05912

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 02.22962	117 55 12.65413	2226882.888	6054090.340	-22.362
2007.00	33 46 02.24593	117 55 12.67102	2226884.56	6054088.94	

References: OCS FILE # OC96/7-5, GEODETIC UNIT

Description:

DESCRIBED BY OCS 2002 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "1F-160-92", SET IN THE SOUTHWEST CORNER OF A 6 FT. BY 4 FT. CONCRETE CATCH BASIN. MONUMENT IS LOCATED IN THE NORTHEAST CORNER OF THE INTERSECTION OF TRASK AVENUE AND HARBOR BOULEVARD, 72 FT. NORTHERLY OF THE CENTERLINE OF TRASK AVENUE AND 52 FT. EASTERLY OF THE CENTERLINE OF HARBOR BOULEVARD. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

