

GPS #: 1540

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation: 2K-20-70

OCS Index Map: 3L

Page/Grid: 708/J-4

City / Location: Brea

Scale Factor: 1.00000978

Ellipsoid Red. Factor: 0.99998287

Combination Factor: 0.99999265

Convergence Angle: -00 54 55.19178

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 56 20.36922	117 54 56.51753	2289338.026	6056450.631	357.932
2007.00	33 56 20.38555	117 54 56.53483	2289339.70	6056449.20	

References: OCS FILE # OC96/7-5, GEODETIC UNIT

Description:

DESCRIBED BY OCS 2001 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "2K-20-70", SET IN THE NORTHEAST CORNER OF A 3 FT. BY 3 FT. CONCRETE PAD. MONUMENT IS LOCATED IN THE SOUTHWEST CORNER OF WHITTIER BOULEVARD AND PUENTE STREET, 50.5 FT. SOUTHERLY FROM THE CENTERLINE OF WHITTIER BOULEVARD AND 21 FT. WESTERLY FROM THE CENTERLINE OF PUENTE STREET. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

