

GPS #: 1543

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation: 1G-127-69

OCS Index Map: 4LA

Page/Grid: 828/C-6

City / Location: Fountain Valley

Scale Factor: 0.99997707

Ellipsoid Red. Factor: 1.00000404

Combination Factor: 0.99998111

Convergence Angle: -00 56 46.74294

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 43 21.13690	117 58 19.51589	2210858.135	6038048.320	-84.449
2007.00	33 43 21.15314	117 58 19.53291	2210859.80	6038046.91	

References: OCS FILE # OC96/7-5, GEODETIC UNIT

Description:

FD 3 3/4" OCS ALUMINUM DISK STAMPED "1G-127-69". LOCATED IN THE SW PART OF THE INTER OF MAGNOLIA ST. AND HEIL AVE., 38' WEST OF THE CENTERLINE OF MAGNOLIA ST., 190' SOUTH OF THE CENTERLINE OF HEIL AVE., 99' NORTH OF THE CENTER OF THE ON RAMP OF THE SAN DIEGO FREEWAY (INTERSTATE 405), SET IN THE TOP OF THE NE CORNER OF A 4' X 8' CONC. CATCH BASIN, 1' HIGHER THAN THE GUTTER.

