

GPS #: 1545

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation: 1G-140-69

OCS Index Map: 3L

Page/Grid: 768/B-7

City / Location: Anaheim

Scale Factor: 0.99998969

Ellipsoid Red. Factor: 1.00000149

Combination Factor: 0.99999118

Convergence Angle: -00 56 53.44418

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



| Epoch Adjustment | Latitude | Longitude | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35 | 33 49 03.76399 | 117 58 31.71065 | 2245504.132 | 6037591.552 | -31.138 |
| 2007.00 | 33 49 03.78005 | 117 58 31.72830 | 2245505.78 | 6037590.09 | |

References: OCS FILE # OC96/7-5, GEODETIC UNIT

Description:

DESCRIBED BY OCS 2002 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "1G-140-69", SET IN THE NORTHWESTERLY CORNER OF A 16 FT. BY 4 FT. CONCRETE CATCH BASIN. MONUMENT IS LOCATED IN THE NORTHEASTERLY CORNER OF THE INTERSECTION OF BALL ROAD AND MAGNOLIA STREET, 46 FT. NORTHERLY OF THE CENTERLINE OF BALL, AND 107 FT. EASTERLY OF THE CENTERLINE OF MAGNOLIA. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

