

GPS #: 1547

Date Destroyed: 5/11/1998

Date Revised:

Benchmark Designation: 2C-67-68

OCS Index Map: 3L

Page/Grid: 738/A-3

City / Location: Unin., Orange County

Scale Factor: 1.00000327

Ellipsoid Red. Factor: 0.99999610

Combination Factor: 0.99999937

Convergence Angle: -00 57 08.81085

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 54 09.14797	117 58 59.67458	2276408.927	6035745.621	81.483
2007.00	33 54 09.16408	117 58 59.69224	2276410.58	6035744.16	

References: OCS FILE # OC96/7-5, GEODETIC UNIT

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 3 3/4" OCS ALUMINUM DISK STAMPED "2C-67-68". LOCATED 0.45 MILE NE ALONG BEACH BLVD. FROM ITS INTER WITH ROSECRANS AVE., 35' NW OF THE CENTERLINE OF THE SW BOUND TRAFFIC LNS OF BEACH BLVD., 70' SW OF A 1.5' HIGH METROPOLITAN WATER DISTRICT MANHOLE, 20' SW OF A LARGE PEPPER TREE, 15' SE OF A 6' HIGH CHAIN LINK FENCE, SET IN THE TOP OF THE CENTER OF THE NORTH CONC. HEADWALL OF A DROP INLET, 3' LOWER THAN THE BLVD.