

GPS #: 1549

Date Destroyed: 1/4/2011
Date Revised: 9/8/2006
Benchmark Designation: Q-1329
OCS Index Map: 4LB
Page/Grid: 857/E-5
City / Location: Huntington Beach

Scale Factor: 0.99997245
Ellipsoid Red. Factor: 1.00000473
Combination Factor: 0.99997719
Convergence Angle: -00 58 47.82412

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 40 52.44367	118 01 59.85676	2196143.132	6019182.805	-98.930
2007.00	33 40 52.46003	118 01 59.87372	2196144.81	6019181.40	

References: OCS FILE # OC96/7-5, GEODETIC UNIT

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: DESCRIBED BY OCS 2006 - FOUND 3 3/4" BRASS DISK STAMPED "Q 1329 1978" DOWN 1.5' SET ON THE TOP OF A 3/4" STEEL ROD. DISK IS LOOSE AND MOVES SLIGHTLY IN THE GROUND PROBABLY DUE TO RECENT GRADING IN AREA. MONUMENT IS LOCATED IN THE NORTHEASTERLY CORNER OF THE INTERSECTION OF PACIFIC COAST HIGHWAY AND SEAPOINT DRIVE 41.7 FT. NORTHERLY OF THE CENTERLINE OF THE NORTHBOUND LANES OF PCH, 9.4 FT. WESTERLY OF THE NORTHWESTERLY CORNER OF A CONCRETE TERRACE AND 0.1 MILES NORTHEASTERLY OF THE CENTERLINE OF SEAPOINT. MONUMENT IS SET LEVEL WITH THE GROUND.

NO
LOCATION
MAP