

**GPS #:** 1550

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation: 1H-103-69

OCS Index Map: 4LB

Page/Grid: 827/E-1

City / Location: Huntington Beach

Scale Factor: 0.99997794

Ellipsoid Red. Factor: 1.00000488

Combination Factor: 0.99998283

Convergence Angle: -00 58 28.50422

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 43 47.44392	118 01 24.69883	2213779.090	6022454.269	-102.067
2007.00	33 43 47.46029	118 01 24.71597	2213780.77	6022452.85	

References: OCS FILE # OC96/7-5, GEODETIC UNIT

## Description:

DESCRIBED BY OCS 2002 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "1H-103-69", SET IN THE NORTHWEST CORNER OF A 5 FT. BY 4 FT. CONCRETE CATCH BASIN. MONUMENT IS LOCATED IN THE SOUTHEAST CORNER OF THE INTERSECTION OF SPRINGDALE STREET AND EDINGER AVENUE, 1 FT. SOUTHERLY OF THE SOUTH CURB FACE ALONG EDINGER AND 168 FT. EASTERLY OF THE PROLONGATION OF THE EAST CURB ALONG SPRINGDALE STREET. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

