

GPS #: 1551

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation: 1H-108-70

OCS Index Map: 4LA

Page/Grid: 827/E-1

City / Location: Westminster

Scale Factor: 0.99998212

Ellipsoid Red. Factor: 1.00000417

Combination Factor: 0.99998629

Convergence Angle: -00 58 32.10870

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 45 47.24769	118 01 31.25817	2225896.780	6022106.550	-87.123
2007.00	33 45 47.26397	118 01 31.27521	2225898.45	6022105.14	

References: OCS FILE # OC96/7-5, GEODETIC UNIT

Description:

DESCRIBED BY OCS 2002 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "1H-108-70", SET IN THE NORTHWESTERLY CORNER OF A 3 FT. BY 4.5 FT. CONCRETE CATCH BASIN. MONUMENT IS LOCATED IN THE SOUTHWESTERLY CORNER OF THE INTERSECTION OF NAVAJO ROAD AND SPRINGDALE STREET, 80 FT. SOUTHERLY OF THE CENTERLINE OF MEINHARDT ROAD AND 32.4 FT. WESTERLY OF THE CENTERLINE OF SPRINGDALE STREET. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

