

GPS #: 1552

Date Destroyed: 11/16/2012

Date Revised: 1/15/2013

Benchmark Designation: 1H-122-70

OCS Index Map: 3L

Page/Grid: 797/E-1

City / Location: Buena Park

Scale Factor: 0.99998955

Ellipsoid Red. Factor: 1.00000347

Combination Factor: 0.99999302

Convergence Angle: -00 58 37.45139

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 49 00.20585	118 01 40.98069	2245412.798	6021618.441	-72.474
2007.00	33 49 00.22194	118 01 40.99834	2245414.45	6021616.98	

References: OCS FILE # OC96/7-5, GEODETIC UNIT

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: DESCRIBED BY OCS 2002 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "1H-122-70", SET IN THE SOUTHWESTERLY CORNER OF A 4.5 FT. BY 15 FT. CONCRETE CATCH BASIN. MONUMENT IS LOCATED IN THE SOUTHEASTERLY CORNER OF THE INTERSECTION OF VALLEY VIEW STREET AND BALL ROAD, 47 FT. EASTERLY OF THE CENTERLINE OF VALLEY VIEW AND 130 FT. SOUTHERLY OF THE CENTERLINE OF BALL ROAD. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

NO
LOCATION
MAP