

GPS #: 1553

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation: P-778-R65

OCS Index Map: 3L

Page/Grid: 767/E-1

City / Location: Buena Park

Scale Factor: 0.99999716

Ellipsoid Red. Factor: 1.00000294

Combination Factor: 1.00000009

Convergence Angle: -00 58 38.41120

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 51 57.72324	118 01 42.72734	2263357.048	6021777.167	-61.358
2007.00	33 51 57.73914	118 01 42.74518	2263358.68	6021775.69	

References: OCS FILE # OC96/7-5, GEODETIC UNIT

Description:

DESCRIBED BY OCS 2002 - FOUND 3 3/4" USC&GS BRONZE DISK STAMPED "P-778-R65", SET IN THE TOP OF A CONCRETE CURB. MONUMENT IS LOCATED IN THE SOUTHEASTERLY CORNER OF THE INTERSECTION OF VALLEY VIEW STREET AND CABALLERO BOULEVARD, 45 FT. EASTERLY OF THE CENTERLINE OF VALLEY VIEW, 68 FT. SOUTHERLY OF THE CENTERLINE OF CABALLERO AND SET ALONG THE EASTERLY CURB OF VALLEY VIEW. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

