

GPS #: 1555

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation: 1A-123-70

OCS Index Map: 4LB

Page/Grid: 796/H-7

City / Location: Seal Beach

Scale Factor: 0.99998280

Ellipsoid Red. Factor: 1.00000502

Combination Factor: 0.99998783

Convergence Angle: -01 00 15.07047

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 06.05880	118 04 38.62575	2228071.247	6006323.604	-105.003
2007.00	33 46 06.07510	118 04 38.64284	2228072.92	6006322.19	

References: OCS FILE # OC96/7-5, GEODETIC UNIT

Description:

DESCRIBED BY OCS 2002 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "1A-123-70", SET IN A CONCRETE CHANNEL WALL. MONUMENT IS LOCATED 0.6 MILES NORTHERLY ALONG SEAL BEACH BOULEVARD FROM ITS INTERSECTION WITH WESTMINSTER AVENUE, 65FT. EASTERLY FROM THE CENTERLINE OF SEAL BEACH BOULEVARD AND 1FT. NORTHEASTERLY OF THE SOUTH END OF A CONCRETE HEADWALL. MONUMENT IS DOWN 1.5FT. FROM THE TOP OF THE HEADWALL.

