

GPS #: 1557

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation: T-280-R75

OCS Index Map: 4LB

Page/Grid: 826/E-4

City / Location: Seal Beach

Scale Factor: 0.99997987

Ellipsoid Red. Factor: 1.00000515

Combination Factor: 0.99998501

Convergence Angle: -01 01 22.74364

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 44 43.90206	118 06 41.77589	2219951.876	5995780.557	-107.519
2007.00	33 44 43.91847	118 06 41.79302	2219953.56	5995779.14	

References: OCS FILE # OC96/7-5, GEODETIC UNIT

Description:

DESCRIBED BY OCS 2001 - FD 3" NATIONAL GEODETIC SURVEY BRASS DISK STAMPED "T-280 RESET 1975", SET IN THE SOUTHWESTERLY CORNER OF A 4 FT. BY 4 FT. CONCRETE CATCH BASIN. MONUMENT IS LOCATED IN THE SOUTHWESTERLY CORNER OF THE INTERSECTION OF MARINA DRIVE AND FIRST STREET, 27 FT. WESTERLY OF THE CENTERLINE OF FIRST STREET AND 46 FT. SOUTHERLY OF THE CENTERLINE OF MARINA DRIVE. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

