

GPS #: 1573

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 971/H-7

City / Location: Dana Point

Scale Factor: 0.99995665

Ellipsoid Red. Factor: 1.00000499

Combination Factor: 0.99996165

Convergence Angle: -00 47 55.37698

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 27 45.33972	117 42 12.54780	2115035.016	6118395.251	-104.311
2007.00	33 27 45.35658	117 42 12.56391	2115036.74	6118393.91	

References: CR 1997-0180

Description:

FD BRASS NAIL AND 3/4" OCS BRASS TIE TAG IN LEAD, SET FLUSH IN CONC. STEP ALONG CONC. SIDEWALK, LOCATED 17' +/- E'LY FROM APPARENT CENTERLINE OF ENSENADA PLACE, SET ON BOTTOM FIRST STEP OF FOUR STEPS, E'LY FROM ORANGE COUNTY YOUTH FACILITY.

