

GPS #: 1574

Date Destroyed: 11/2/2015

Date Revised: 11/2/2015

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 971/H-7

City / Location: Dana Point

Scale Factor: 0.99995661

Ellipsoid Red. Factor: 1.00000502

Combination Factor: 0.99996163

Convergence Angle: -00 47 46.62697

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 27 41.62734	117 41 56.62473	2114641.048	6119738.861	-104.898
2007.00	33 27 41.64419	117 41 56.64083	2114642.77	6119737.52	

References: CR 1997-0186

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD BRASS NAIL AND 3/4" OCS BRASS TIE TAG IN LEAD, SET FLUSH IN CENTER OF CONC. SIDEWALK, LOCATED 4.5' +/- NW'LY FROM CONC. ANGLE POINT HANDRAIL, 50' +/- W'LY FROM APPARENT CENTERLINE OF ISLAND WAY DR.

