

GPS #: 1575

Date Destroyed:
Date Revised: 4/23/1996
Benchmark Designation:
OCS Index Map: 6LA
Page/Grid: 971/H-7
City / Location: Dana Point

Scale Factor: 0.99995660
Ellipsoid Red. Factor: 1.00000502
Combination Factor: 0.99996162
Convergence Angle: -00 47 43.18688

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 27 40.16711	117 41 50.36452	2114486.103	6120267.113	-104.872
2007.00	33 27 40.18391	117 41 50.38065	2114487.82	6120265.77	

References: CR 1997-0185

Description:

FD 1 1/4" OCS BRASS TAG STAMPED "31+00 5/85"
EPOXIED IN CENTER OF CONC. SIDEWALK,
LOCATED 350' +/- W'LY FROM THE CENTERLINE
PROD OF CASITAS PLACE, IN BETWEEN BOAT
DOCKS "D" AND "E".

