

GPS #: **1578**

Date Destroyed: **12/1/2001**
Date Revised: **4/23/1996**
Benchmark Designation:
OCS Index Map: **6LA**
Page/Grid: **971/J-7**
City / Location: **Dana Point**

Scale Factor: **0.99995652**
Ellipsoid Red. Factor: **1.00000479**
Combination Factor: **0.99996132**
Convergence Angle: **-00 47 28.28380**

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 27 33.14499	117 41 23.24422	2113744.601	6122554.681	-100.193
2007.00	33 27 33.16191	117 41 23.26021	2113746.33	6122553.35	

References: CR 1997-0182

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD LARGE PUNCHED BRASS SPIKE WITH 1 1/2" BRASS "USCE-LA DIST" WASHER, SET FLUSH IN 2' DIA. IRREGULAR SHAPED CONC. MONUMENT ON TOP OF ROCK JETTY, LOCATED 65' +/- S'LY OF LARGE EUCALYPTUS TREE, 6.5' SW'LY FROM N'LY SIGN POST, SIGN STATING "BREAK WATER SUBJECT TO HIGH SURF".

NO
LOCATION
MAP