

**GPS #:** **1586**

Date Destroyed:

Date Revised: 8/23/1996

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 800/H-1

City / Location: Orange

Scale Factor: 0.99998876

Ellipsoid Red. Factor: 0.99997736

Combination Factor: 0.99996612

Convergence Angle: -00 50 06.16849

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 48 40.76113	117 46 10.55930	2242206.081	6100083.052	473.044
2007.00	33 48 40.77733	117 46 10.57596	2242207.74	6100081.67	

References: OCS FILE # OP95/6-24N, GEODETIC UNIT

**Description:**

FD 2 1/2" BRASS DISK STAMPED "OCFCD VP-19" SET IN 14" DIA. CONC. MONUMENT FLUSH WITH GROUND LOCATED FROM THE INTER OF SANTIAGO CANYON RD. AND LOLITA ST., PROCEED ALONG MOST SE'LY A.C. RD. OF LOLITA ST. 0.1 MILE TO THE ENTRANCE OF THE VILLA PARK DAM. PROCEED THROUGH GATE AND ALONG A.C. RD. 0.1 MILE TO THE TOP OF THE GRAVEL AUXILIARY DAM ON RIGHT. TURN RIGHT AND PROCEED ALONG GRAVEL DAM 0.17 MILE TO SAID MONUMENT LOCATED ALONG THE TOP OF DAM AT THE END OF THE LEFT HAND CURVE.

