

GPS #: 1587

Date Destroyed:

Date Revised: 8/23/1996

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 800/H-1

City / Location: Orange

Scale Factor: 0.99998871

Ellipsoid Red. Factor: 0.99997734

Combination Factor: 0.99996605

Convergence Angle: -00 50 05.48250

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 48 39.54236	117 46 09.31096	2242081.361	6100186.579	473.503
2007.00	33 48 39.55857	117 46 09.32759	2242083.02	6100185.20	

References: OCS FILE # OP95/6-24N, GEODETIC UNIT

Description:

FD 2" I.P. WITH A 2 1/2" BRASS OCS DISK STAMPED "100+00 JAN 1980" IN 6" DIA. CONC. COLLAR FLUSH WITH GROUND LOCATED FROM THE INTER OF SANTIAGO CANYON RD. AND LOLITA ST., PROCEED ALONG MOST SE'LY A.C. RD. OF LOLITA ST. 0.1 MILE TO THE ENTRANCE OF THE VILLA PARK DAM. PROCEED THROUGH GATE AND ALONG A.C. RD. 0.1 MILE TO THE TOP OF THE GRAVEL AUXILIARY DAM ON RIGHT. TURN RIGHT AND PROCEED ALONG GRAVEL DAM TO ITS TERMINUS NEXT TO THE CEMETERY. SAID MONUMENT IS LOCATED 15' NW'LY FROM THE CHAIN LINK FENCE.

