

**GPS #:** 1590

Date Destroyed:

Date Revised: 8/23/1996

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 770/H-7

City / Location: Orange

Scale Factor: 0.99998920

Ellipsoid Red. Factor: 0.99997541

Combination Factor: 0.99996461

Convergence Angle: -00 50 04.73610

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 48 51.77433	117 46 07.95268	2243316.018	6100319.189	513.972
2007.00	33 48 51.79047	117 46 07.96943	2243317.67	6100317.80	

References: OCS FILE # OP95/6-24N, GEODETIC UNIT

### Description:

FD 2 1/2" BRASS OCS CAP STAMPED "VP-32 JAN 1980" SET IN 6" DIA. CONC. MONUMENT UP 0.1' LOCATED FROM THE INTER OF SANTIAGO CANYON RD. AND LOLITA ST., PROCEED ALONG MOST SE'LY A.C. RD. OF LOLITA ST. 0.1 MILE TO THE ENTRANCE OF THE VILLA PARK DAM. PROCEED THROUGH GATE DAM ON RIGHT. PARK HERE AND HIKE UPHILL N'LY TO SAID MONUMENT LOCATED ALONG THE TOP OF HILL 35'+/- W'LY OF TELEPHONE POLE.

