

GPS #: 1600

Date Destroyed: 7/25/2000

Date Revised: 8/23/1996

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 770/H-7

City / Location: Orange

Scale Factor: 0.99998966

Ellipsoid Red. Factor: 0.99998167

Combination Factor: 0.99997132

Convergence Angle: -00 49 58.92981

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 49 02.85644	117 45 57.38652	2244423.152	6101226.911	383.142
2007.00	33 49 02.87264	117 45 57.40330	2244424.81	6101225.52	

References: OCS FILE # OP95/6-26N, GEODETIC UNIT

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 2" BRASS OCFCD DISK STAMPED "VP-14" SET IN CONC. DOWN 0.3' IN DIRT LOCATED FROM THE INTER OF SANTIAGO CANYON RD. AND LOLITA ST., PROCEED ALONG MOST SE'LY A.C. RD. OF LOLITA ST. 0.1 MILE TO THE ENTRANCE OF THE VILLA PARK DAM. PROCEED THROUGH GATE AND ALONG A.C. RD. 0.1 MILE TO THE TOP OF THE GRAVEL AUXILIARY DAM ON RIGHT. CONTINUE ALONG SAID RD. 0.2 MILE TO DIRT RD. ON LEFT JUST BEFORE BRIDGE CROSSING OVER SPILLWAY. TURN LEFT AND PROCEED DOWNHILL ALONG SAID RD. 500'+/- TO SHARP RIGHT TURN. TURN RIGHT AND CONTINUE E'LY ALONG DIRT RD., ACROSS CREEK, 0.2 MILE TO SAID MONUMENT LOCATED 10'+/- W'LY OF RD., NEXT TO A 2' DIA. ROCK, 25'+/- E'LY OF AN OAK TREE.