

GPS #: **1609R1**

Date Destroyed:

Date Revised: 6/26/2001

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 972/C-2

City / Location: San Juan Capistrano

Scale Factor: 0.99995823

Ellipsoid Red. Factor: 1.00000090

Combination Factor: 0.99995913

Convergence Angle: -00 46 37.47591

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 29 53.04151	117 39 50.78515	2127776.203	6130578.876	
2007.00	33 29 53.05851	117 39 50.80132	2127777.94	6130577.53	

References: PMB 230/9-10, CR 2001-1017

Description:

FD PK NAIL AND WASHER STAMPED "LS 5411" IN LIEU OF PUNCHED LARGE ROUND HEAD SPIKE WITH WASHER. MONUMENT WAS RESET PER CORNER RECORD # 2001-1017B. MONUMENT IS LOCATED AT THE VISUAL CENTERLINE "T" INTER OF DEL OBISPO ST. AND RIOS ST., 37' +/- W'LY OF THE MOST W'LY RAIL OF THE RAILRD. TRACKS.

