

GPS #: 1630

Date Destroyed:
Date Revised: 8/23/1996
Benchmark Designation:
OCS Index Map: 6LA
Page/Grid: 972/B-3
City / Location: San Juan Capistrano

Scale Factor: 0.99995785
Ellipsoid Red. Factor: 1.00000220
Combination Factor: 0.99996005
Convergence Angle: -00 46 53.56664

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 29 24.89871	117 40 20.06670	2124965.638	6128060.667	-46.063
2007.00	33 29 24.91566	117 40 20.08288	2124967.37	6128059.32	

References: MM 481/10-11

Description:

FD GEAR SPIKE WITH BRASS TAG STAMPED "RCE (UNREADABLE)" FLUSH IN A.C. LOCATED IN THE SOUTHBOUND TRAVEL LN. IN A CURVE, ALONG ALIPAZ AVE., W'LY ALONG THE PROD OF A 4' HIGH BLOCK WALL, 39' +/- NW'LY FROM POWER POLE # 324526.

