

GPS #: **1643**

Date Destroyed: **10/30/1998**
Date Revised: **9/16/2010**
Benchmark Designation:
OCS Index Map: **5LB**
Page/Grid: **801/A-4**
City / Location: **Unin., Orange County**

Scale Factor: **0.99998532**
Ellipsoid Red. Factor: **0.99997401**
Combination Factor: **0.99995933**
Convergence Angle: **-00 49 33.27322**

*Factors and Convergence Angle based on
the 1991.35 Epoch Adjustment positions.*

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 47 13.27479	117 45 10.69722	2233290.348	6105006.148	543.060
2007.00	33 47 13.29114	117 45 10.71347	2233292.02	6105004.80	

References: A/NE-IRV, 1364-1389, RSB 173/1-10

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED
BOX) - ORIGINAL DESCRIPTION BEING: FD PUNCHED
HEX BAR IN OCS WELL MONUMENT, DOWN 1.8',
LOCATED IN THE EAST BOUND RIGHT LN. ALONG
THE CENTERLINE OF SANTIAGO CANYON RD., 0.6
MILES E'LY FROM ITS INTER WITH JAMBOREE RD.
PER RSB 173/1-10.