

GPS #: **1648**

Date Destroyed: **10/30/1998**
Date Revised: **9/16/2010**
Benchmark Designation:
OCS Index Map: **5LB**
Page/Grid: **801/B-5**
City / Location: **Unin., Orange County**

Scale Factor: **0.99998466**
Ellipsoid Red. Factor: **0.99996997**
Combination Factor: **0.99995463**
Convergence Angle: **-00 49 21.50811**

*Factors and Convergence Angle based on
the 1991.35 Epoch Adjustment positions.*

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 55.92123	117 44 49.28733	2231510.379	6106787.824	627.591
2007.00	33 46 55.93757	117 44 49.30353	2231512.05	6106786.48	

References: A/NE-IRV, 1364-1389, RSB 173/1-10

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED
BOX) - ORIGINAL DESCRIPTION BEING: FD PUNCHED
HEX BAR IN OCS WELL MONUMENT, DOWN 2.0',
LOCATED IN THE EAST BOUND RIGHT LN. ALONG
THE CENTERLINE OF SANTIAGO CANYON RD., 1.2
MILES E'LY FROM ITS INTER WITH JAMBOREE RD.
PER RSB 173/1-10.