

GPS #: **1649**

Date Destroyed: **10/30/1998**
Date Revised: **9/16/2010**
Benchmark Designation:
OCS Index Map: **5LB**
Page/Grid: **801/B-5**
City / Location: **Unin., Orange County**

Scale Factor: **0.99998390**
Ellipsoid Red. Factor: **0.99996434**
Combination Factor: **0.99994824**
Convergence Angle: **-00 49 19.23839**

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 35.57014	117 44 45.15694	2229448.436	6107106.910	745.186
2007.00	33 46 35.58641	117 44 45.17309	2229450.10	6107105.57	

References: A/NE-IRV, 1364-1389, RSB 173/1-10

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD PUNCHED HEX BAR IN OCS WELL MONUMENT, DOWN 2.0', LOCATED IN THE EAST BOUND RIGHT LN. ALONG THE CENTERLINE OF SANTIAGO CANYON RD., 1.6 MILES E'LY FROM ITS INTER WITH JAMBOREE RD. PER RSB 173/1-10.