

GPS #: 1650

Date Destroyed: 10/30/1998
Date Revised: 9/16/2010
Benchmark Designation:
OCS Index Map: 5LB
Page/Grid: 801/B-6
City / Location: Unin., Orange County

Scale Factor: 0.99998354
Ellipsoid Red. Factor: 0.99996087
Combination Factor: 0.99994441
Convergence Angle: -00 49 13.39605

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 25.99318	117 44 34.52519	2228467.605	6107990.411	817.794
2007.00	33 46 26.00955	117 44 34.54136	2228469.28	6107989.07	

References: A/NE-IRV, 1364-1389, RSB 173/1-10

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD PUNCHED HEX BAR IN OCS WELL MONUMENT, LOCATED IN THE EAST BOUND RIGHT LN. ALONG THE CENTERLINE OF SANTIAGO CANYON RD., 1.85 MILES E'LY FROM ITS INTER WITH JAMBOREE RD. PER RSB 173/1-10.