

GPS #: 1655

Date Destroyed: 10/30/1998
Date Revised: 9/16/2010
Benchmark Designation:
OCS Index Map: 5LB
Page/Grid: 801/B-6
City / Location: Unin., Orange County

Scale Factor: 0.99998316
Ellipsoid Red. Factor: 0.99995886
Combination Factor: 0.99994202
Convergence Angle: -00 49 07.60987

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 15.82435	117 44 23.99562	2227427.102	6108864.488	859.746
2007.00	33 46 15.84076	117 44 24.01175	2227428.78	6108863.15	

References: A/NE-IRV, 1364-1389, RSB 173/1-10

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD PUNCHED HEX BAR IN OCS WELL MONUMENT, LOCATED IN THE EAST BOUND LN. ALONG THE CENTERLINE OF SANTIAGO CANYON RD., 2.1 MILES E'LY FROM ITS INTER WITH JAMBOREE RD., 100' +/- W'LY FROM THE SANTIAGO CANYON LANDFILL A.C. RD. PER RSB 173/1-10.