

**GPS #:** 1670

Date Destroyed:

Date Revised: 8/23/1996

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 973/A-1

City / Location: Unin., Orange County

Scale Factor: 0.99995846

Ellipsoid Red. Factor: 0.99995153

Combination Factor: 0.99990999

Convergence Angle: -00 44 30.14854

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



| Epoch Adjustment | Latitude       | Longitude       | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35          | 33 30 09.49220 | 117 35 59.07760 | 2129178.776   | 6150220.278  | 1012.984              |
| 2007.00          | 33 30 09.50908 | 117 35 59.09355 | 2129180.50    | 6150218.95   |                       |

References: RSB 161/42-47

**Description:**

FD 2" I.P. WITH ALUMINUM CAP STAMPED "COUNTY OF ORANGE SURVEYOR BOUNDARY 1972 RCE 6978". (LOCATED ALONG THE PRIMA DESHECHA LANDFILL BOUNDARY)

