

GPS #: **1893**

Date Destroyed:

Date Revised: 1/21/1999

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 890/G-7

City / Location: Irvine

Scale Factor: 0.99996574

Ellipsoid Red. Factor: 0.99995622

Combination Factor: 0.99992196

Convergence Angle: -00 50 46.84139

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 36 37.26905	117 47 24.57496	2169174.289	6092758.140	914.864
2007.00	33 36 37.28578	117 47 24.59158	2169176.00	6092756.76	

References: OCS FILE # 989DD7313, CR 1999-0016, RSB 179/1-10

Description:

FD 3 3/4" OCS ALUMINUM DISK STAMPED "SHADY #2" IN 1' DIAMETER CONCRETE COLLAR UP 0.2' IN DIRT. LOCATED N'LY FROM THE SAN JOAQUIN TRANSPORTATION CORRIDOR ALONG THE MAIN RIDGE BETWEEN BOMMER CANYON AND SHADY CANYON.

