

GPS #: 1915

Date Destroyed:

Date Revised: 12/20/2000

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 889/B-1

City / Location: Costa Mesa

Scale Factor: 0.99997019

Ellipsoid Red. Factor: 1.00000220

Combination Factor: 0.99997238

Convergence Angle: -00 54 20.71798

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 32.49006	117 53 53.78287	2187386.526	6060125.185	-45.876
2007.00	33 39 32.50650	117 53 53.79969	2187388.21	6060123.79	

References: JWA GPS Survey - 12/2000

Description:

DESCRIBED BY OCS 2001 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "CM-25-77", SET IN THE WESTERLY CORNER OF A 4 FT. BY 6 FT. CONCRETE CATCH BASIN. MONUMENT IS LOCATED IN THE NORTHERLY CORNER OF THE INTERSECTION OF ELDEN AVENUE AND MONTE VISTA AVENUE, 21 FT. NORTHERLY OF THE CENTERLINE OF MONTE VISTA AND 55.5 WESTERLY OF THE CENTERLINE OF ELDEN AVENUE. MONUMENT IS SET LEVEL WITH THE TOP OF THE CURB.

