

GPS #: **2150**

Date Destroyed:

Date Revised: 9/24/2007

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 799/E-2

City / Location: Orange

Scale Factor: 0.99998800

Ellipsoid Red. Factor: 0.99999767

Combination Factor: 0.99998567

Convergence Angle: -00 53 29.35708

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 48 21.82524	117 52 20.31742	2240762.264	6068857.017	48.697
2007.00	33 48 21.84141	117 52 20.33441	2240763.92	6068855.61	

References: RSB 142/21-24, CR 2007-0938, CR 2007-1540

Description:

FD PUNCHED HEX BAR DOWN 1.5' IN OCS WELL MONUMENT. STATION IS LOCATED AT THE B.C. ON KATELLA AVE. WEST OF STRUCK AVE.

