

GPS #: **2152**

Date Destroyed:

Date Revised: 8/23/1996

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 799/E-1

City / Location: Anaheim

Scale Factor: 0.99998891

Ellipsoid Red. Factor: 0.99999736

Combination Factor: 0.99998626

Convergence Angle: -00 53 33.02017

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 48 44.40012	117 52 26.98345	2243052.703	6068330.124	55.256
2007.00	33 48 44.41610	117 52 27.00063	2243054.34	6068328.70	

References: RSB 142/21-24

Description:

FD 2" I.P. WITH OCFCD R/W BRASS TAG DOWN 1.8'.
STATION IS LOCATED 150'+/- WEST OF PHOENIX CLUB DR., 22.5' NORTH OF THE N'LY RAIL OF SOUTHERN PACIFIC R.R.

