

GPS #: **2153**

Date Destroyed: **7/25/2000**

Date Revised: **8/23/1996**

Benchmark Designation:

OCS Index Map: **2L**

Page/Grid: **799/F-1**

City / Location: **Orange**

Scale Factor: **0.99998902**

Ellipsoid Red. Factor: **0.99999712**

Combination Factor: **0.99998614**

Convergence Angle: **-00 53 19.79263**

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 48 47.24697	117 52 02.91225	2243308.868	6070365.421	60.121
2007.00	33 48 47.26310	117 52 02.92940	2243310.52	6070364.00	

References: **RSB 105/26**

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 1 1/2" I.P. WITH 3/4" TAG STAMPED "LS 4453" DOWN 1.0'. STATION IS LOCATED SOUTH OF YALE AVE., 50' +/- WEST OF MAIN ST., 8' +/- WEST OF CURB FACE, 0.5' SOUTH OF A WOOD HEADER, AND 300' +/- NORTH OF S.P.R.R. TRACKS.