

GPS #: **2155R1**

Date Destroyed:

Date Revised: 5/6/2017

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 799/F-1

City / Location: Orange

Scale Factor: 0.99998909

Ellipsoid Red. Factor: 0.99999707

Combination Factor: 0.99998616

Convergence Angle: -00 53 19.55889

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 48 48.91393	117 52 02.48690	2243476.794	6070403.921	61.171
2007.00	33 48 48.93010	117 52 02.50404	2243478.45	6070402.50	

References: PMB 223/13-14, CR 2002-0384, 2002-0526

Description:

FD PK NAIL & WASHER "LS 6970" IN LIU OF ORIGINAL MONUMENT BEING GEAR SPIKE AND BRASS TAG STAMPED "RCE 23927" DOWN 0.1'. MONUMENT RESET PER CR # 2002-0526. STATION IS LOCATED NEAR THE CENTERLINE OF MAIN ST., 10'+/- SOUTH OF THE CENTERLINE OF YALE AVE.

NO
LOCATION
MAP