

GPS #: **2162**

Date Destroyed:

Date Revised: 8/23/1996

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 799/D-7

City / Location: Anaheim

Scale Factor: 0.99998975

Ellipsoid Red. Factor: 0.99999548

Combination Factor: 0.99998522

Convergence Angle: -00 53 37.82954

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 49 05.10637	117 52 35.73542	2245157.034	6067624.392	94.534
2007.00	33 49 05.12234	117 52 35.75270	2245158.67	6067622.96	

References: MM 410/41-45

Description:

FD PUNCHED SPIKE AND 1" CDH TAG, FLUSH IN A.C. MEDIAN. STATION IS LOCATED ON THE CENTERLINE OF BALL RD., 85'+/- WEST OF THE CENTERLINE OF THE 57 FREEWAY.

