

GPS #: **2170**

Date Destroyed:

Date Revised: 2/23/1997

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 865/C-7

City / Location: Unin., Orange County

Scale Factor: 0.99996995

Ellipsoid Red. Factor: 0.99984932

Combination Factor: 0.99981927

Convergence Angle: -00 38 42.28692

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 23.75152	117 25 26.04666	2184549.793	6204450.998	3149.357
2007.00	33 39 23.76865	117 25 26.06213	2184551.54	6204449.71	

References: RSB 160/17-32

Description:

FD 2" IP WITH 3 1/2" ALUMINUM U.S. DEPARTMENT OF AGRICULTURE FOREST SERVICE DISK STAMPED "T6S R5W S8 S17 LS 4926 1994 UNLAWFUL TO DISTURB, CADASTRAL SURVEY" UP 1.0' SURROUNDED BY STONES. LOCATED FROM THE 5 FREEWAY AND ORTEGA HWY. PROCEED E'LY AND N'LY 22.6 MILES ON ORTEGA HWY. TURN LEFT, E'LY, ON LONG CANYON RD.(LOS PINOS/McCONVILLE EXIT) CONTINUE 0.6 MILES, TURN RIGHT, N'LY, INTO THE McCONVILLE RESORT CONTINUE THROUGH RIGHT, E'LY, GATE (PRIVATELY LOCKED -PH. # 909-678-4494, MR. NILSON) MAKE A HARD RIGHT CONTINUE ALONG RD. (NOW DIRT) 0.3 MILES TO POWER LINE AT END OF "AIRSTRIIP LANDING". CONTINUE ALONG IN A NE'LY DIRECTION 0.05 MILES TO A FORK. BEAR LEFT, N'LY, APPROXIMATELY 0.1 MILES TO A TRAIL THAT GOES IN A N'LY DIRECTION UP A STEEP HILL. HIKE 4000' ALONG THE TRAIL TO THE DOWN SIDE OF THE SECOND SADDLE. THE MONUMENT IS ABOUT 5' E'LY OFF THE SIDE OF THE TRAIL.

