

GPS #: **2172**

Date Destroyed:

Date Revised: 2/23/1997

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 895/C-2

City / Location: Unin., Orange County

Scale Factor: 0.99996856

Ellipsoid Red. Factor: 0.99988794

Combination Factor: 0.99985651

Convergence Angle: -00 38 42.31316

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 31.55284	117 25 26.09442	2179273.961	6204387.558	2341.938
2007.00	33 38 31.57000	117 25 26.11001	2179275.71	6204386.26	

References: RSB 160/17-32

Description:

FD 2" IP WITH 3 1/4" ALUMINUM U.S. DEPARTMENT OF AGRICULTURE FOREST SERVICE DISK STAMPED "1/4 S17 S20 LS 4550 1980 UNLAWFUL TO DISTURB, CADASTRAL SURVEY" UP 0.2' IN 3' DIA. PILE OF GRANITE STONES. LOCATED FROM THE 5 FREEWAY AND ORTEGA HWY. PROCEED E'LY AND N'LY 22.6 MILES ON ORTEGA HWY. TURN LEFT, E'LY, ON LONG CANYON RD.(LOS PINOS/McCONVILLE EXIT) CONTINUE 0.6 MILES, TURN RIGHT, N'LY, INTO THE McCONVILLE RESORT CONTINUE THROUGH RIGHT, E'LY, GATE (PRIVATELY LOCKED -PH. # 909-678-4494, MR. NILSON) MAKE A HARD RIGHT CONTINUE ALONG RD. (NOW DIRT) 0.2 MILES TO A JUNCTION ON RIGHT OF "AIR STRIP". THENCE E'LY 0.1 MILE TO A THREE WAY INTER TAKE THE CENTER RD., SE'LY, 0.2 MILE TO THE END THE MONUMENT IS 20' E'LY.

