

**GPS #:** **2173**

Date Destroyed:

Date Revised: 2/23/1997

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 895/C-2

City / Location: Unin., Orange County

Scale Factor: 0.99996856

Ellipsoid Red. Factor: 0.99988614

Combination Factor: 0.99985470

Convergence Angle: -00 38 46.91822

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 31.59101	117 25 34.47460	2179285.803	6203679.161	2379.707
2007.00	33 38 31.60814	117 25 34.49022	2179287.55	6203677.86	

References: RSB 160/17-32

**Description:**

FD 2 " IP WITH BRASS TAG STAMPED "LS 5558" UP 0.3' FROM THE 5 FREEWAY AND ORTEGA HWY. PROCEED E'LY AND N'LY 22.6 MILES ON ORTEGA HWY. TURN LEFT, E'LY, ON LONG CANYON RD.(LOS PINOS/McCONVILLE EXIT) CONTINUE 0.6 MILES, TURN RIGHT, N'LY, INTO THE MC CONVILLE RESORT CONTINUE THROUGH RIGHT, E'LY, GATE (PRIVATELY LOCKED -PH. # 909-678-4494, MR. NILSON) MAKE A HARD RIGHT CONTINUE ALONG RD. (NOW DIRT) 0.2 MILES TO A JUNCTION ON RIGHT OF "AIR STRIP" THENCE E'LY 0.1 MILE TO A THREE WAY INTER TAKE THE CENTER RD.,SE'LY, 0.1 MILE TO A FLAT PARKING AREA ON RIGHT. HIKE S'LY APPROX. 300' TO S'LY LINE OF SEC 17 (INDICATED BY FOREST SERVICE PADDLES). CONTINUE W'LY ALONG SAID S'LY LINE APPROX. 300' TO COUNTY LINE.

