

GPS #: **2174**

Date Destroyed:

Date Revised: 2/23/1997

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 895/B-2

City / Location: Unin., Orange County

Scale Factor: 0.99996856

Ellipsoid Red. Factor: 0.99988702

Combination Factor: 0.99985558

Convergence Angle: -00 38 59.99150

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 31.70023	117 25 58.26508	2179319.596	6201668.097	2361.278
2007.00	33 38 31.71744	117 25 58.28066	2179321.35	6201666.80	

References: RSB 160/17-32

Description:

FD 2" IP WITH 2 1/2" X 1" THICK BRASS DISK
STAMPED "U.S. GENERAL LAND OFFICE SURVEY
1938 \$250 FOR REMOVAL T6S R5W S18 S17 S19 S20"
0.4' ABOVE GROUND. LOCATED FROM THE 5
FREEWAY AND ORTEGA HWY. PROCEED E'LY 22.6
MILES ON ORTEGA HWY. TURN LEFT ON LONG
CANYON RD.(LOS PINOS/McCONVILLE EXIT)
CONTINUE E'LY 0.7 MILES, TURN RIGHT, N'LY,
CONTINUE 500' TO STEEL GATE. MONUMENT IS ON
RIGHT, E'LY 20'.

