

GPS #: 2175

Date Destroyed:

Date Revised: 2/23/1997

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 895/D-1

City / Location: Unin., Orange County

Scale Factor: 0.99996942

Ellipsoid Red. Factor: 0.99988095

Combination Factor: 0.99985038

Convergence Angle: -00 38 33.01164

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 04.35446	117 25 09.16772	2182573.240	6205855.681	2488.043
2007.00	33 39 04.37163	117 25 09.18334	2182574.99	6205854.38	

References: RSB 160/17-32

Description:

FD 3/4" IP WITH PLASTIC PLUG STAMPED "LS 4384" DOWN 0.2' LOCATED FROM THE 5 FREEWAY AND ORTEGA HWY. PROCEED E'LY 23.8 MILES ALONG ORTEGA HWY. TURN LEFT, N'LY, ON EL CARISO RD. CONTINUE ALONG 0.1 MILES TO A FORK (BETWEEN PARCELS 2 & 3 PER RS 23/91-92) BEAR LEFT, NW'LY, 800' TO A "T" INTER @ 32442 EL CARISO RD., TURN LEFT, W'LY, 900' TO THE COUNTY BOUNDARY LINE PER SAME RS. LOCATED 207' NE OF POWER POLE #2245920E.

