

GPS #: **2176**

Date Destroyed:

Date Revised: 2/23/1997

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 895/D-1

City / Location: Unin., Orange County

Scale Factor: 0.99996938

Ellipsoid Red. Factor: 0.99988017

Combination Factor: 0.99984955

Convergence Angle: -00 38 34.37305

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 02.78092	117 25 11.64519	2182416.546	6205644.479	2504.460
2007.00	33 39 02.79802	117 25 11.66078	2182418.29	6205643.18	

References: RSB 160/17-32

Description:

FD 1" IP UP 0.2', SET 1 1/4" BRASS OCS TAG AND TACK IN CENTER OF PIPE STAMPED "GPS 2176 9-96". LOCATED FROM THE 5 FREEWAY AND ORTEGA HWY. PROCEED E'LY 23.8 MILES ALONG ORTEGA HWY. TURN LEFT, N'LY, ON EL CARISO RD. CONTINUE ALONG 0.1 MILES TO A FORK (BETWEEN PARCELS 2 & 3 PER RS 23/91-92) BEAR LEFT, NW'LY, 800' TO A "T" INTER @ 32442 EL CARISO RD., TURN LEFT, W'LY, 900' TO THE COUNTY LINE PER SAME RS. LOCATED 100' SW OF POWER POLE #2245920E.

